

Full Height Turnstile

Features

- ★ Pass speed 30 per / min.
- ★ Water proof & dust proof
- ★ Installation place out door & In door
- ★ Can be upgraded
- ★ Weatherproof
- ★ Fine finish
- ★ Low maintenance
- ★ Longer functional life



Descriptions

- Throughput: 12 to 15 persons per minute with access control.
- Rotor Arm height from Ground: 2000 mm.
- 90 deg. stop (4 Arms)
- Positive action lock is provided to prevent multiple persons access or exit
- Anti-back up device to prevent reverse rotation after 25deg.
- The structure is made of heavy gauge mild steel round & Square pipe with epoxy powder coated finish or stainless steel bars to ensure long trouble free operating life and requiring minimal maintenance
- A Self-centered mechanism with hydraulic damping to ensure Complete rotation of the tripod head to reset position
- Temp. Range: -5 deg. to 55 deg. Centigrade
- Power Consumption: 50 watts
- Direction of entry: Bi-directional / Unidirectional (Controlled and free rotation)
- This is compatible to any access-exit control/ attendance/pay roll system/ device
- It has side handrail to prevent forced side entry of persons

LOKPAL INDUSTRIES